



INTEGRATED COST/SCHEDULE RISK MANAGEMENT

Michael Carrancho, PE
Chief of Engineering & Design
Smithsonian Institution
17 October 2019

Smithsonian Around the Globe



Smithsonian Facilities By the Numbers


- 19 Museums + 1 Zoo
- 9 Research Centers
- 154 million artifacts
- 2 million library volumes
- 29 million in-person visitors
- 13 million square feet
- 43,000 acres of land
- 28,000 equipment assets
- 13,000 volunteers
- 6,675 employees
- 600 Buildings
- 300 Structures




National Air and Space Museum – Mall Building Facts

- 1958** – planned location authorized by President Eisenhower
- 1971** – Congress appropriated \$41 million for construction
- 1972-1973** – design by Hellmuth, Obata & Kassabaum (HOK)
- 1976** – opened to the public on July 1 as part of the Nation's Bicentennial
- 1995-1997** – last previous major work on stone façade
- 1997-2001** – skylight & window wall replacement


- Mechanical systems date to the building's construction
- Stone façade is primary & exclusive weather barrier
- Building dimensions are (747,877 sf):
 - 209 meters (685 feet) in length
 - 69 meters (225 feet) in width
 - 25 meters (83 feet) in height
- In parallel alignment with National Gallery of Art building on opposite side of the Mall



The need to address the façade...



The Challenge



Logistics

Revitalization/Transformation Artifact/Object Summary

Total number of objects to be moved: **2,733**
Total number of artifacts to be moved: **2,430**

<input type="checkbox"/> NASM NMB Artifacts		<input type="checkbox"/> Loans for Transformation	
▪ Total artifacts in NMB:	1,606	▪ Number of loans not renewed from NMB:	202
▪ Moving out of NMB:	768	▪ Number of loans renewed from NMB:	86
▪ Returning to NMB:	786	▪ Number of new loans to NASM:	117
▪ Not currently on exhibit at NMB:	1,465	▪ Number of recalled loans (NASM artifacts):	308
▪ Protect in Place (PIP):	10		
<input type="checkbox"/> Garber Objects		<input type="checkbox"/> Valuable Curatorial Objects (VCOs)	
▪ Number coming to NMB for Transformation:	75	▪ Total number in NMB:	169
 		▪ Number moving out:	108
<input type="checkbox"/> UHC Objects		▪ Number returning to NMB:	50
▪ Number coming to NMB for Transformation:	1,039		

Studying the needs

- 2013 Preliminary studies undertaken
 - Envelope Study
 - Feasibility Study
 - Sustainability Study
- Integrated Cost/Schedule Risk Management
 - February 2016 Risk Assessment (Schematic Design)
 - November 2016 Risk Assessment update (35% Design)
 - October 2019 Risk Assessment (GMP Design)

Assessing the needs

- Pre-requisites for Integrated Risk Management
 - Detailed Cost and Schedule information is required
 - Cost-loaded Critical Path Schedule is Developed
 - Knowledgeable and dedicated subject matter experts
 - Consultant expertise in conducting workshops and analysis
 - Time

Why Risk Management?

BEST PRACTICES CHECKLISTS

1. Best Practices Checklist: The Estimate	45
2. Best Practices Checklist: Purpose, Scope, and Schedule	49
3. Best Practices Checklist: Cost Assessment Team	56
4. Best Practices Checklist: Technical Baseline Description	64
5. Best Practices Checklist: Work Breakdown Structure	78
6. Best Practices Checklist: Ground Rules and Assumptions	88
7. Best Practices Checklist: Data	105
8. Best Practices Checklist: Developing a Point Estimate	123
9. Best Practices Checklist: Estimating Software Costs	145
11. Best Practices Checklist: Cost Risk and Uncertainty	176
13. Best Practices Checklist: Documenting the Estimate	196
14. Best Practices Checklist: Presenting the Estimate to Management	198
15. Best Practices Checklist: Managing Program Costs: Planning	240
16. Best Practices Checklist: Managing Program Costs: Execution	270
17. Best Practices Checklist: Managing Program Costs: Updating	295

This is a work of the U.S. government and is not subject to copyright protection in the United States. The published product may be reproduced and distributed in its entirety without further permission from GAO. However, because this work may contain copyrighted images or other material, permission from the copyright holder may be necessary if you wish to reproduce this material separately.

Probabilistic Risk Management in Design and Construction Projects (Best Practices)

RT-280
2010 - 2012

- Publications: 4
- Presentations: 3
- Tools: 2


KA: Risk Management

1 : Level of Risk Management


There are 3 processes that organizations can use to implement more advanced project risk management approaches, including probabilistic analysis. This process comprises three levels, each of which offers clear benefits: risk identification, deterministic analysis, and probabilistic analysis.

Risk	Category
Poor soil conditions may require deep foundations, resulting in cost increase.	Cost
Utility relocation delay could result in longer schedule.	Schedule

Level 1: Risk Identification is the formal act of identifying risks and opportunities for projects. Typically, this includes the use of a risk checklist and/or the start of a risk register.




Level 2: Deterministic Risk Analysis is the act of analyzing risks through a single-point estimate of potential impacts. Typically, this involves a probability × impact matrix, a prioritized list of risks, and/or an expected value for contingency allocation of schedule or cost.



Level 3: Probabilistic Risk Analysis is the act of analyzing risk through probability distribution estimates of potential impact, known as Monte Carlo simulations. Typically, this approach involves cumulative distributions of potential outcomes and determination of the probability of meeting project targets.

Overview of the Process



The Costs

Summary of Risk Analysis Results: Cost Objectives for NASM Project & DCC Storage Module 1					
No.	Program Description	SI CWE Budget Amount	CPM Summary Schedule Amount	Risk Analysis P-80 Value	P-80 Budget Shortall
1	Total NASM Program Budget without Contingency	\$561,492,562	\$561,492,562		
2	NASM Construction Contingency	\$114,542,438	\$114,542,438		
3	Total NASM Program Budget with Contingency	\$676,035,000	\$676,035,000	\$680,432,000	(\$4,397,000)
4	DCC Storage Module without Contingency	\$53,804,361	\$53,804,361		
5	DCC Storage Module Contingency	\$4,199,687	\$4,199,687		
6	DCC Storage Module with Contingency	\$58,004,048	\$58,004,048	\$63,855,000	(\$5,850,952)
5	Total SI Program Budget with Contingency including DCC	\$734,039,048	\$734,039,048	\$744,287,000	(\$10,247,952)

The Schedule

Summary of Milestone Dates: Planned Sequence from 35% DD and CPM Summary Schedule				
No.	Work Scope	Planned Timeline ¹	35% DD Planned Completion Date ²	CPM Summary Schedule Date ³
	Temporary Space	Months 0 - 4	3/15/2018	3/30/2018
DCC	DCC Storage Module	19 Months		1/31/2019⁴
Zone 1	Demount	Months 5 - 9	2/15/2019	11/5/2018
	Construction	Months 10 - 23	1/15/2020	1/13/2020
	Remount		2/15/2021	8/16/2024
Zone 2	Demount		2/15/2019	10/30/2018
	Construction	Months 14 - 38	1/15/2020	1/17/2020
	Remount		1/15/2021	10/1/2020
Zone 3	Demount		8/15/2019	6/8/2021
	Construction	Months 27-41	5/15/2021	8/10/2022
	Remount		12/15/2021	11/16/2022
Zone 4	Demount		10/15/2019	1/10/2020
	Construction	Months 26-56	6/15/2021	8/10/2022
	Remount		8/15/2021	3/2/2022
Zone 5	Demount		5/15/2022	6/8/2021
	Construction	Months 35-68	7/15/2023	8/10/2022
	Remount		1/15/2023	12/28/2022
Zone 6	Demount		5/15/2022	3/24/2023
	Construction	Months 56-75	2/15/2024	2/2/2024
	Remount	Months 73-84	11/15/2024	11/29/2024
Zone 7	Demount		2/15/2022	12/30/2022
	Construction	Months 56-75	2/15/2024	3/22/2024
	Remount	Months 71-82	9/15/2024	1/31/2025
	Project Construction Completion		2/15/2024	10/25/2024
	Project Final Completion		9/15/2024	1/31/2025


The People

No.	Name	No.	Name
1	Ann Powell	24	John Bixler
2	Ann Trowbridge	25	Josh Shaw
3	Barbara Faust	26	Josh Stewart
4	Bill Donnelly	27	Juan Puente
5	Brian Temme	28	Ken Johnson
6	Cecelia Mayer	29	Kevin Blanchard
7	Charles Chandler	30	Larry Barr
8	Charles Obi	31	Leora Mirvish
9	Claire Siedschlag	32	Mark Kornmann
10	Colin MacKillop	33	Mary Kfoury
11	Darick Allan	34	Meg Caulk
12	David Hay	35	Meg Caulk
13	David Voyles	36	Michael Kilby
14	Debbie Nauta-Rodriguez	37	Mike Carrancho
15	Deborah Palazzo	38	Mike Henry
16	Derek Ross	39	Rick Flansburg
17	Doug Hall	40	Rob Shaw
18	Douglass Erickson	41	Sarah Billington
19	Ed Rynne	42	Sharon Park
20	Ed Stroczyński	43	Stephen Schluth
21	Elizabeth Fedowitz	44	Susan Lake
22	Eve Errikson	45	Tom Dempsey
23	Hugh Meehan		

The Workshops



Projecting the Impacts



The Worksheets

RISK ID	Risk Statement (cause, risk, impact)	Probability	Impact on Time			Impact on Cost			Activities /Resources Affected	Risk Mitigation Proposed in 2015; Notes; Suggested Mitigations in 2016
			Low	ML	High	Low	ML	High		
1006	Mitigation Proposed (2016, at 35% DD) =====>	Reprioritize budget and or scope items within or outside the project. Monitoring of budget line item for supervision and administration. Based on NMAAHC actual SIOH costs of approximately 5% the 5% S&A amount for NASM, if not reduced and if not of excessive duration, should be sufficient.								Reprioritize budget and or scope items within or outside the project. Monitoring of budget line item for supervision and administration.
	Post Mitigation Risk Parameters =====>	55%				1.00	1.15	1.30		
1007	Stone Risk - production/quarry. The yield of the Tennessee Marble company is still uncertain despite the feasibility (the yield in the new quarry may be less than what's stated or assumed in the estimate). Quality of stone may not match the spec requiring further drilling delaying the production	50%	1.20	1.25	2.00	1.05	1.10	1.25	Stone Fabricate and Inspect	1) Prior to purchase, conduct independent drilling/boring at and near quarry to determine extent of vein, quantity, quality, consistency (including battery of lab analyses of the stone). 2) Widen acceptable color range, pending approval by Agencies. 3) Pre-purchase & quarry at least 50% of projected stone to process into blocks for sorting/analysis (100% if possible) to get ahead of the schedule
	Mitigation Proposed (2016, at 35% DD) =====>	1) Project schedule slippage has relieved some of the production pressure on Tennessee pink. 2) Si will, either through AE, CM, or CM@risk, conduct independent drilling/boring at and near quarry to determine extent of vein, quantity, quality, consistency (including battery of lab analyses of the stone). 3) Si is evaluating other stone and materials for the cladding other than Tennessee Pink 4) Widen acceptable color range, pending approval by Agencies. 5) Pre-purchase & quarry at least 50% of projected stone to process into blocks for sorting/analysis (100% if possible) to get ahead of the schedule We believe the original probability of 50% was low and that the correct mitigated probability is 50%								
	Post Mitigation Risk Parameters =====>	50%	1.20	1.25	2.00	1.05	1.10	1.25		
1008	Stone Risk - delivery (included in 1007)	50%	1.10	1.15	1.25				Not modeled in risk analysis; for Project Risk Register	1) Purchase enough surplus stone blocks to store at quarry to prevent delay in delivery. 2) Identify local storage site for finished panels to accommodate delays in construction schedule. 3) Detail interfaces of exterior wall to allow sequencing flexibility (i.e. so stone can be installed last). 4) Panelized cladding system helps address deficient panel replacement and related delivery delays.
	Mitigation Proposed (2016, at 35% DD) =====>	1) Project schedule slippage has reduced pressure on delivery schedule, especially early in project 2) Introduction of Rain Screen envelope system has lessened stone cladding placement as the critical path 3) Potential use of other cladding material can significantly reduce delivery schedule risk 4) Purchase enough surplus stone blocks to store at quarry to prevent delay in delivery. 5) Identify local storage site for finished panels to accommodate delays in construction schedule. 6) Detail interfaces of exterior wall to allow sequencing flexibility (i.e. so stone can be installed last). 7) Panelized cladding system helps address deficient panel replacement and related delivery delays. Risk probability based on the use of Tennessee Pink								
	Post Mitigation Risk Parameters =====>	40%	1.10	1.15	1.25					
1009	Major design defect or error	35%	1.00	1.05	1.10	1.00	1.00	1.05	Not modeled in risk analysis; for Project Risk Register	1) Peer reviews are on-going. 2) BIM pre bid clash detection is planned 3) Pre bid mock ups are being planned 4) Validate design through testing and mock ups 5) Design assist/ early contractor involvement being considered.
	Mitigation Proposed =====>	Multiple levels of review/ CMC involvement, preview of subs, Peer reviews								
	Post Mitigation Risk Parameters =====>	15%	1.00							
1010	Client initiated/requested changes	80%	1.05	1.10	1.30	1.05	1.10	1.30	Office space, swing space for staff, artifacts	"Change Management Board" has been incorporated in the Project Management Plan (PMP). Engage all parties in discussions early and often. Interview stakeholders before SD410 process to identify needs. Ensure all stakeholders are part of the SD410 process. Provide flexibility in the design to account for changing needs of the staff/Museum/SE. Plan for allocation of staff (HR). Manage/prioritize different agendas; what takes precedence (artifacts, revenue, space). Improve communication from executive team as to what the priority is. Establish/utilize the change management board.
	Mitigation Proposed (2016, at 35% DD) =====>									
	Post Mitigation Risk Parameters =====>	70%	1.05	1.10	1.30	1.05	1.10	1.30		


Developing Mitigations

1007	Stone Risk - production/quarry. The yield of the Tennessee Marble company is still uncertain despite the feasibility (the yield in the new quarry may be less than what's stated or assumed in the estimate). Quality of stone may not match the spec requiring further drilling delaying the production	50%	1.20	1.25	2.00	1.05	1.10	1.25	Stone Fabricate and Inspect
	Mitigation Proposed (2016, at 35% DD) =====>	<p>1) Project schedule slippage has relieved some of the production pressure on Tennessee pink.</p> <p>2) SI will, either through AE, CM, or CM@risk, conduct independent drilling/boring at and near quarry to determine extent of vein, quantity, quality, consistency (including battery of lab analyses of the stone).</p> <p>3) SI is evaluating other stone and materials for the cladding other than Tennessee Pink</p> <p>4) Widen acceptable color range, pending approval by Agencies.</p> <p>5) Pre-purchase & quarry at least 50% of projected stone to process into blocks for sorting/analysis (100% if possible) to get ahead of the schedule</p> <p>We believe the original probability of 50% was low and that the correct mitigated probability is 50%</p>							
	Post Mitigation Risk Parameters =====>	50%	1.20	1.25	2.00	1.05	1.10	1.25	


Cost Confidence Pre-mitigation




Schedule Confidence Pre-mitigation



Cost Confidence Post-mitigation



Schedule Confidence Post-mitigation



The Cost Risk Drivers

Top 20 Cost Risk Drivers		
No.	Risk Description	Cost Impact
1	Resource Uncertainty	\$29,467,000
2	Client initiated/requested changes	\$26,972,900
3	Stone Risk - production/fabrication	\$11,368,700
4	West End is the choke point for everything coming in and out of the building (hazmat, stone, exhibits, artifacts)	\$7,188,340
5	At the current staffing level in Collections, challenging to properly focus on major projects that include Revitalization, NASM Master Plan, Suitland Master Plan for DCC, UHC-buildout, and building upgrades at Garber	\$5,727,580
6	Lack of adequate SI "Supervision and Administration" budget	\$2,477,810
7	Swing Space - Design and Construction of Swing Space Overall Duration (planned duration 11 month may not be adequate)	\$2,135,390
8	Proposed schedule for re-mount/reinstallation of 10-12 months may be insufficient.	\$2,074,530
9	Duration Uncertainty	\$1,856,730
10	Cladding - delayed selection of cladding material (e.g., due to lack of consensus within or outside SI) and its impact on agency review and approval process, issuance of 65% DD, material testing and construction documentation	\$1,765,660
11	Unforeseen conditions	\$1,682,980
12	Unintended consequences of perceived good ideas (best intentions) from newer parties brought onboard for various studies might slow the design and construction process; cumulative effect on design completion	\$1,655,170
13	Changes in senior leadership might impact the project due to the change in priorities	\$1,559,170
14	DCC - Client requested changes	\$1,546,150
15	DCC - Unforeseen Conditions	\$1,478,650
16	Agency reviews may result in additional design changes and time	\$1,251,390
17	Risk of a large batch of stone falling during construction (due to vibration, etc. - during de-installation) impacting construction - in the construction zone	\$1,173,890
18	Lack of adequate staff within SI to manage NASM Project	\$927,505
19	DCC - Delayed or insufficient funding	\$617,515
20	Current re-mounting schedule has not accounted for additional artifacts, yet to be selected from collection currently outside of Mall Building.	\$541,653

The Schedule Risk Drivers

Top 20 Schedule Risk Drivers		
No.	Risk Description	Time Impact (days)
1	Stone Risk - production/fabrication	107
2	Client initiated/requested changes	45
3	West End is the choke point for everything coming in and out of the building (hazmat, stone, exhibits, artifacts)	36
4	Proposed schedule for re-mount/reinstallation of 10-12 months may be insufficient.	27
5	Duration Uncertainty	25
6	Cladding - delayed selection of cladding material (e.g., due to lack of consensus within or outside SI) and its impact on agency review and approval process, issuance of 65% DD, material testing and construction documentation	13
7	Current re-mounting schedule has not accounted for additional artifacts, yet to be selected from collection currently outside of Mall Building.	8
8	Lack of adequate staff within SI to manage NASM Project	6
9	Swing Space - Design and Construction of Swing Space Overall Duration (planned duration 11 month may not be adequate)	5
10	Unforeseen conditions	5
11	Risk of a large batch of stone falling during construction (due to vibration, etc. - during de-installation) impacting construction - in the construction zone	5
12	Agency reviews may result in additional design changes and time	4
13	At the current staffing level in Collections, challenging to properly focus on major projects that include Revitalization, NASM Master Plan, Suitland Master Plan for DCC, UHC-buildout, and building upgrades at Garber	3
14	Unintended consequences of perceived good ideas (best intentions) from newer parties brought onboard for various studies might slow the design and construction process; cumulative effect on design completion	3
15	Lack of defined schedule for exhibit re-installation will have impact to the construction (also Risk ID 1020)	1
16	Price above Engineer's Estimate	1
17	Resource Uncertainty	0
18	Lack of adequate SI "Supervision and Administration" budget	0
19	Changes in senior leadership might impact the project due to the change in priorities	0
20	DCC - Client requested changes	0

The Summary Results

Summary of Risk Analysis Results: Cost Objectives for NASM Project & DCC Storage Module 1					
No.	Program Description	SI CWE Budget Amount	CPM Summary Schedule Amount	Risk Analysis P-80 Value	P-80 Budget Shortall
1	Total NASM Program Budget without Contingency	\$561,492,562	\$561,492,562		
2	NASM Construction Contingency	\$114,542,438	\$114,542,438		
3	Total NASM Program Budget with Contingency	\$676,035,000	\$676,035,000	\$680,432,000	(\$4,397,000)
4	DCC Storage Module without Contingency	\$53,804,361	\$53,804,361		
5	DCC Storage Module Contingency	\$4,199,687	\$4,199,687		
6	DCC Storage Module with Contingency	\$58,004,048	\$58,004,048	\$63,855,000	(\$5,850,952)
5	Total SI Program Budget with Contingency including DCC	\$734,039,048	\$734,039,048	\$744,287,000	(\$10,247,952)

Summary of Risk Analysis Results for SI NASM Project: Schedule Objectives						
No.	Milestones	Planned Timeline*	Planned Date	CPM Schedule Date	Risk Analysis P-80 Date	Risk Analysis P-90 Date
1	Project Construction Completion	Months 59-76	2/15/2024	10/25/2024	6/10/2026	9/2/2026
2	Final Remount Exhibit Completion	Months 75-86	11/15/2024	1/31/2025	1/20/2027	4/16/2027

* Assumes NTP on 11/30/2017

Follow on actions

- Generated risk register to manage mitigations
- Quarterly review of register and mitigations
- Conducted quarry visits and stone tests
- Made stone selection based on risk analysis
- We've executed as a CM@Risk w/design assist
- Performed Value Engineering exercises
- The museum director hired a Deputy and additional staff including a scheduler
- We've done a bunch of other things (partnering, PMP, BIM PxP)

OK What if I don't have a \$1 billion Project?

- CII Best Practice Provides 3 Tiers
- Provides Spreadsheet Tool
- Tier 1 Identify Risk
- Tier 2 Deterministic Risk
- Tier 3 Probabilistic Risk (Integrated)

Probabilistic Risk Management in Design and Construction Projects (Best Prac

RT-280
2010 - 2012

- Publications: 4
- Presentations: 3
- Tools: 2

KA: Risk Management

Instructions

Risk Register Sheet Overview

Below is a list of each sheet and the purpose it serves in creating the final risk register.

Instructions	Provides necessary instructions and definitions for the risk register tool. The sheet serves as a reference and requires no input.
Input Sheet	Defines values for impact and probability. Values are used in deterministic calculations. Default values can be used, if desired.
Level 1 - Identification	Risk identification is the first step in the creation of Level 2 Deterministic Risk Analysis. Enter initial risks on this sheet, including risk description, project phase, and category of impact (time or cost).
Level 2 - Deterministic	Deterministic risk analysis is the second step in the creation of the Level 2 risk register. Each risk is rated on a qualitative impact and probability scale. In addition, the user can manually enter the expected risk impact and probability value. This sheet will populate the risk mean value (i.e. the most likely case) and overall risk ranking for each identified risk. This is the last sheet to complete to create the Level 2 risk register. The input focuses on mitigating and monitoring the risks. The user can identify response strategies, assign key individuals, and note potential trigger events. The user can also estimate the cost of mitigation and then re-rank the risks' impacts and probabilities. This sheet will populate the post-mitigated risk mean value (i.e. the most likely case) and give the overall risk ranking for each identified risk.
Allocation & Risk M.	This is the final sheet of the Level 2 risk register. The entire sheet is auto-populated on the basis of the data entered in the previous sheets.
Summary	

Initial Data

Initial project data is required to create the risk register. Below, please enter the following approximate values: Project Value (USD), Length of Project (Days), and Value of One (1) Day Delay (in USD). Data will be used in the subsequent sheets to produce the final risk register.

Initial Project Data Input	
Project Value (Unescalated USD)¹:	\$14,000,000
Length of Project (Calendar Days)²:	238
Value of One (1) Day Delay (USD): <i>Example: \$10,000</i>	\$5,000

¹ Project value should include construction, design, and/or land purchase, depending upon the goals of the risk analysis. Project value should include estimated contingency for this input.

² Length of project should be to mid-point of construction and should include construction and/or design, depending upon the goals of the risk analysis.

CII Phases (Referenced in Risk Identification Sheet)

Front End Planning	From definition of business need to authorization of total project budget
Detail Engineering	From design basis through release of all approved drawings and specifications for construction
Procurement	From the procurement plan for engineered equipment through the delivery of engineered equipment to the site
Construction	From commencement of foundations or piles to completion of the mechanical system
Start-up/Commissioning	From completion of mechanical systems through the transfer of the project to user/operator

Input

INPUT SHEET

Before completing the subsequent sheets, first complete this input sheet on the basis of the specific project being assessed. Instructions for each input section are located on the right side of this page.

Category of Impact				
Cost				
Description	Percent of Project Value		Mean Value	
	L	H	(Dollars)	
VL Insignificant Cost Increase	0%	0%	\$0	
L Minimal Cost Increase	0%	6%	\$420,000	
M Significant Cost Increase	6%	12%	\$1,260,000	
H Very Significant Cost Increase	12%	20%	\$2,240,000	
VH Critical Cost Increase	20%	40%	\$4,200,000	

Schedule				
Description	Value		Mean Value	
	L	H	(Days)	(Dollars)
VL Impact recoverable without affecting critical path	0%	1%	1.2	\$5,950
L Impact recoverable affecting critical path	1%	2%	3.6	\$17,850
M Critical path affected	2%	5%	8.3	\$41,650
H Restructuring of project required	5%	10%	17.9	\$89,250
VH Major restructuring of project required	10%	20%	35.7	\$178,500

Cost Instructions

For each description level, in the orange boxes, enter the high (H) percent of project value. Low percent values will automatically populate. Default percent values are provided.

Schedule Instructions

For each description level, in the orange boxes, enter the high (H) percent of project length. Low percent values will automatically populate. Default percent values are provided.

Risk Probability Ranking		
Description	Value	
	L	H
vl Very low likelihood of occurring	0%	10%
l Low likelihood of occurring	10%	30%
m Medium likelihood of occurring	30%	50%
h High likelihood of occurring	50%	70%
vh Very high likelihood of occurring	70%	100%

Probability Instructions

For each probability description level, in the orange boxes, enter the high (H) percentage value correspondent to that level. Low percent values will automatically populate. Default percent values are provided.

Deterministic Output Rankings							
		Pxl Heat Map					
Probability	vh						
	h						
	m						
	l						
	vl						
			VL	L	M	H	VH
		Impact					

Ranking Definition	
High	Unacceptable. Major impact on project goals. Different approach
Med	Some impact on project goals. Different approach may be required.
Low	Minimum impact. Minimum oversight needed to ensure risk

Level 1 Identification

LEVEL 1 - RISK IDENTIFICATION						
Item	Status	Date Identified	Brief Risk Description	Detailed Risk Description	CII Project Phases	Category of Impact
62	Active	10/04/18	Construction Security	New OPS cameras may be required to account for new visitor/staff ingress and egress methods	Construction	Cost
63	Active	10/23/18	Visitor Flow	Construction Equipment will interfere with musuem visitation	Construction	Schedule
64	Active	10/23/18	Parking	Contractor personnel parking costs. Limited free parking for construction staff	Construction	Cost
65	Active	10/23/18	Competition method	How we procure the construction could affect the construction cost	Procurement	Cost
66	Active	10/23/18	Sustainable Demolition	Reducing construciton waste stream will be a transferred cost	Construction	Cost
67	Active	10/23/18	Protection / Replacement of gardens	Lots of travel in area and the HMSG has an extensively planted grounds that could be	Construction	Cost
68	Active	10/23/18	Timing of procurement	If this project is competing in a saturated construciton market place prices will be affected	Procurement	Cost
69	Active	10/23/18	Events near site	Not only do museum activities affect construciton but also activity near the HMSG	Construction	Cost
70	Active	10/23/18	Events near site	Not only do museum activities affect construciton but also activity near the HMSG	Construction	Schedule

Level 2 Deterministic

LEVEL 2 - DETERMINISTIC								
Item #	Brief Risk Description	Category of Impact	Pre-Mitigated Risk Ranking					
			Most Likely Impact		Most Likely Probability		Risk Mean Value (Dollars)	Overall Risk Ranking
			Qualitative Value	Quantitative Mean Value (Dollars or Day)	Qualitative Value	Quantitative Mean Value		
Auto	Auto	Auto	Drop Down (Selection Required)	Auto (Manual Override)	Drop Down (Selection Required)	Auto (Manual Override)	Auto	Auto
1	Panel Condition	Cost	Very High	\$4,200,000	Medium	40%	\$1,680,000	High
2	Panel Condition	Schedule	Very High	36	Medium	40%	\$71,400	High
3	Proper Construction Equipment	Schedule	Very High	36	Low	20%	\$35,700	Med
4	Weather	Schedule	High	18	High	60%	\$53,550	High
5	Weather	Cost	Medium	\$1,260,000	Medium	40%	\$504,000	Med
6	No fall protection	Cost	Medium	\$1,260,000	Very High	85%	\$1,071,000	High
7	Adequate Storage for Panels	Cost	Medium	\$1,260,000	Very High	85%	\$1,071,000	High
8	Adequate Storage for Panels	Schedule	Medium	8	Very High	85%	\$35,403	High
9	Construction Trailer	Cost	Low	\$420,000	High	60%	\$252,000	Med
10	Paver Damage	Cost	Medium	\$1,260,000	High	60%	\$756,000	Med
11	Visitor Flow	Cost	Medium	\$1,260,000	High	60%	\$756,000	Med
12	Dust Control	Cost	Low	\$420,000	High	60%	\$252,000	Med
13	Dust Control	Schedule	Low	4	Low	20%	\$3,570	Low

Probability - Quality
Select the approximate probability of the

Mitigations

RISK MANAGEMENT														
Item #	Brief Risk Description	Response Action/Strategy	Response Action/Strategy Description	Responsible Individual	Cost of Response Action	Monitoring & Updating		Post-Mitigated Risk Ranking						
						Trigger Events	Risk Resolution Date	Most Likely Impact		Most Likely Probability		Risk Mean Value	Risk Mean Value + Cost of Mitigation	Overall Risk Ranking
								Qualitative Value	Quantitative Mean Value (Dollars or Day)	Qualitative Value	Quantitative Value			
Auto	Auto	Drop Down	Manual	Manual	Manual	Manual	Manual (MM/DD/YY)	Drop Down	Auto (Manual Override)	Drop Down	Auto (Manual Override)	Auto	Auto	Auto
62	Construction Security	Mitigate	Design Team having forethought of the phasing and ingress and	AE	\$0	Design	01/01/19	Low	\$420,000	High	60%	\$252,000	\$252,000	Med
63	Visitor Flow	Accept	NA	na	\$0	na	01/01/19	High	18	High	60%	\$53,550	\$53,550	High
64	Parking	Mitigate	Negotiate with city for spaces	PM	\$0	Design	01/01/19	Low	\$420,000	Low	20%	\$84,000	\$84,000	Low
65	Competition method	Mitigate	More competition is good	CM	\$0	Construction	01/01/20	Low	\$420,000	Very Low	5%	\$21,000	\$21,000	Low
66	Sustainable Demolition	Accept	NA	NA	\$0	Construction	01/01/20	Low	\$420,000	Low	20%	\$84,000	\$84,000	Low
67	Protection / Replacement of gardens	Mitigate	Have SG provide the protection	SG	\$20,000	Construction	01/01/20	Low	\$420,000	Low	20%	\$84,000	\$104,000	Low
68	Timing of procurement	Mitigate	Pick a better time for procurement	CM	\$0	Construction	01/01/20	Very Low	\$0	Very Low	5%	\$0	\$0	Low
69	Events near site	Mitigate	Getting event schedules early to mitigate impacts	CM	\$0	Construction	01/01/20	Very Low	\$0	Very Low	5%	\$0	\$0	Low
70	Events near site	Mitigate	Getting event schedules early to mitigate impacts	CM	\$0	Construction	01/01/20	Very Low	1	Very Low	5%	\$298	\$298	Low

Summary

RISK REGISTER

RISK REGISTER													
RISK IDENTIFICATION					ANALYSIS			RISK MANAGEMENT					
Item	Status	Date Identified	Brief Risk Description	CII Project Phases	Category of Impact	Pre-Mitigated Risk Mean Value	Pre-Mitigated Risk Ranking	Response Action/Strategy Description	Responsible Individual	Monitoring & Updating		Post-Mitigated Risk Mean Value	Post-Mitigated Risk Ranking
										Trigger Events	Risk Resolution Date		
1	Active	10/01/18	Panel Condition	Construction	Cost	\$1,680,000	High	Test Samples. Rigging Hooks for removal techniques	Architect/3rd Party	Award	10/01/19	\$327,000	Med
2	Active	10/01/18	Panel Condition	Construction	Schedule	\$71,400	High	Test Samples. Rigging Hooks for removal techniques	Architect/3rd Party	Award	10/01/18	\$16,660	Med
3	Active	10/01/18	Proper Construction Equipment	Construction	Schedule	\$35,700	Med	Provide parameters and equipment requirements in the contract documents	KTR	NTP	10/01/20	\$375,000	Low
4	Active	10/18/18	Weather	Construction	Schedule	\$53,550	High	Track NOAA data	KTR	NTP	10/01/19	\$0	Low
5	Active	10/01/18	Weather	Construction	Cost	\$504,000	Med	Track NOAA data	KTR	NTP	10/01/20	\$504,000	Med
6	Active	10/01/18	No fall protection	Construction	Cost	\$1,071,000	High	KTR supplies their own fall protection equipment and plan	KTR	RFP	01/01/20	\$166,000	Low
7	Active	10/01/18	Adequate Storage for Panels	Construction	Cost	\$1,071,000	High	Find additional space alternate locationis. Store on Grass racking system	SI	AE Award	10/01/18	\$84,000	Low
8	Active	10/01/18	Adequate Storage for Panels	Construction	Schedule	\$35,403	High	Find additional space alternate locationis. Store on Grass racking system	SI	AE Award	10/02/18	\$3,570	Low
9	Active	10/01/18	Construction Trailer	Construction	Cost	\$252,000	Med	Contractor buys and installs trailer	KTR	NTP	10/01/20	\$134,000	Low
10	Active	10/01/20	Paver Damage	Construction	Cost	\$756,000	Med	KTR required tolay protection	KTR	RFP	01/01/20	\$184,000	Low
11	Active	10/01/18	Visitor Flow	Construction	Cost	\$756,000	Med	KTR required to build tunnels	KTR	RFP	01/01/20	\$184,000	Low

SI Implementation

- SI has piloted on 2 projects, plans for more
- Hirshhorn Envelope Replacement project ~\$20 million
- Hirshhorn Vertical Transportation Repair ~\$5
- Interviewed approximately 10-15 Subject Matter Experts
- Took approximately 12-20 hours of time

Benefits

- Got SME's thinking about risks to project
- Identified mitigations and generated risk/mitigation register
- Identified impacts to schedule and cost of project
- Got team thinking about creative solutions
- Achieved a diversified perspective on the project

Limitations

- Tends to overstate individual cost and schedule impacts (based on inputs)
- Difficult to determine a reasonable cost/duration contingency (no histograms)



Questions?

Michael Carrancho
carrancom@si.edu
202-633-6598