




Temporary Natural Gas Generators and Drake Decommissioning Society of American Military Engineers

January 11, 2022


E. Thomas Cook, PE
Colorado Springs Utilities

Agenda

- Temporary Natural Gas Generators (TNGG)
- Drake Decommissioning




Energy Supply Generation Portfolio




Project Timeline

Need to address the level of organization and speed that this project is undergoing,
Major hurdles that happened as the project has transitioned into reality.

















Inputs to Portfolio Recommendation




IRP Attributes and Weighting

Attribute	Weight
Reliability	32%
Ability to react to variable or extreme daily operating conditions (i.e., the lights stay on).	
Cost/Implementation	22%
Cost-effectively maintain competitive, affordable rates and the financial health of the utility to drive a strong economy with ability to execute portfolio in desired timeframe.	
Environment/Stewardship	22%
Sustainably grow renewable portfolio, reduce carbon footprint and meet all environmental regulations while responsibly protecting and supporting quality of life now and for the future.	
Flexibility/Diversity	14%
Ability to adapt to regulatory and market disruptions by balancing multiple types of generators and fuel sources, including distributed generation, and reduce reliance on fossil fuels.	
Innovation	10%
Proactively and responsibly integrate technologies and programs.	

Electric Integrated Resource Plan | pathways and portfolios selected by UPAC for further evaluation


	Portfolio	Carbon targets	Rank (12)	2023	2026	2030	2035	2040	2050
Reference case	R						Drake, Birdsall retire Gas		
	1	2030 80% 2050 90%					Drake & Birdsall retire Gas/renewable/ storage		
Pathway B	5	2030 80% 2050 90%			Drake retire Gas & DSM	Nixon 1 retire Gas & DSM	Birdsall retire Renewable/ storage/DSM		
	9	2030 80% 2050 90%			Drake retire	Nixon 1 retire	Birdsall retire		
Pathway C	10	2030 80% 2050 100%			Renewable/ storage/DSM	Renewable/ storage/DSM	Renewable/ storage/DSM		Front Range & Nixon 2-3 retire Renewable/ storage/DSM
	11	2030 80% 2050 100%			Drake retire Non-carbon & DSM	Nixon 1 retire Non-carbon & DSM	Birdsall retire Non-carbon & DSM		Front Range & Nixon 2-3 retire Non-carbon & DSM
Pathway E	12			Drake retire	Nixon 1 retire		Birdsall retire		
	16	2030 80% 2050 90%		Small, mobile natural gas generator	Gas/renewable/ storage/DSM	Nixon 1 retire	Gas/renewable/ storage/DSM		
	17					Nixon 1 retire Non-carbon & DSM	Birdsall retire Non-carbon & DSM		
Pathway F	15	2030 100%				Drake, Nixon 1-3, Birdsall, Front Range retire Renewable/ storage/DSM			
	18	2040 100%					Drake & Birdsall retire Renewable/ storage/DSM	Nixon 1-3 & Front Range retire Renewable/ storage/DSM	
	19	2050 100%					Renewable/ storage/DSM		Nixon 1-3 & Front Range retire Renewable/ storage/DSM

a greener **FUTURE**



Future Generation

Solar/Wind	Increasing
Gas	Decrease
Coal	Ceasing




Quiz Question #1

How many coal plants were retired during the period of 2015-2020?

Why?

- Carbon reduction goals (80% by 2030)
- Community interest in decommissioning of Drake
- 2023: Total solar capacity – 265 MW
- Fast-start, reliable generation will help maintain system reliability
- Planning reserves requirement
- Dual fuel robustness



Solution

Temporary Natural Gas Generators (TNGG)

- Temporary at the Drake site
- Modular Gas Turbines

Why Modular Combustion Turbines?

Fast-start, reliable

- Great for load following (renewables)
 - 8-minute fast start
- Better power / weight ratio
- Smaller footprint
- Short Lead time

Low cost of ownership

- Minimal staff required
- Lower O&M costs
 - No water injection
 - No starts-based maintenance

Fast construction timeline

- Minor modification air permit
- We have rights to the site

Relocatable

- Ability to move the units when our transmission system is upgraded
- Skidded design

Why Modular Combustion Turbines?

Key LM2500+G4 Xpress Unit Characteristics

- 34.6% efficiency (gas, site conditions; note Drake plant is 28.3% efficient)
- Dry Low NOx (DLE)
- Full Load in 8 minutes
- Dual fuel

LM2500 History

- Aviation Legacy: C5/DC-10 aircraft
 - Stationary Generation
 - Nautical Install: 1st Unit 1975 (DD963)
- > 500 million operating hours




Schedule Overview

Internal Work

- Project Management
- Preliminary Design
- Substation
- Gas Supply
- Electrical / Piping

External Work

- Permitting
- Final Design
- Construction
- Installation
- Commissioning



Quiz Question #2

How many land-based LM2500's are installed in the US?

First Steps: Belt Decom and Site Prep

BC1 Belt



First Steps: Belt Decom and Site Prep

BC2 Belt




First Steps: Belt Decom and Site Prep

UTUF / Stackout Belt



TNGG Project Scope




TNGG Engine Installation

LM2500XPRESS Pre-Assembled Modules

Allows for rapid deployment and minimal site installation

Configuration Shown: Gas Only, RH Exhaust, Static Filter




Installation



Major Project Completion Milestones

- Engine Contract 10/1/20
- Engineering Contract 11/16/20
- Construction Finished 6/1/22
- Commercial Operation 12/31/22

Initial milestones



Colorado Springs Utilities

Initial Rendering



Dispatching

NOW

- Replace Drake generation
- Planned for 2% - 4% capacity factor
- Additional analysis
 - Emissions Compliance
 - Cold weather operations

FUTURE

- As we join new markets, these units will add a lot of value
 - Fast start, peaking
- Could see increase in capacity factor



Quiz Question #3

What aircraft is the LM2500 engine commonly found on?



Colorado Springs Utilities
It's how we're all connected

Martin Drake Decommissioning

Decommissioning

- Education
 - Market Intelligence
 - Scope of Work, Define End Point
- Define the Approach
- Scope
- Schedule
- Budget
- Resources



Decommissioning Market Intelligence

1. Market Overview

- Market size, growth rate and outlook
- Market drivers and constraints
- Regulatory trends impacting the market

2. Decommission, Demolition and remediation – approach and techniques

Coal plant demolition techniques / costs

Remediation techniques – (Site / Ash ponds)

Abatement techniques for Asbestos and Lead

3. Hypothesis to be tested

Best method to decommission underground piping (removal, fill, abandonment in place or others?)

Flexibility/potential of brownfield sites to be transitioned into greenfields



Decommissioning Market Intelligence, continued

4. Industry Best Practices

- Approach adopted to optimize salvage value such as contract tied to index price
- Cost estimation for powerplant decommissioning.

5. Contractor Landscape

- List of key contractors with capability matrix for services like decommissioning, deconstruction, and remediation
- Detailed profiles for key contractors



Decommissioning Target

Brownfield ← Target

“A property, the expansion, redevelopment, or reuse of which may be complicated by the presence or potential presence of a hazardous substance, pollutant, or contaminant.” (defined by federal statute).

- After decommissioning, major issues of concern for power plant brownfields include soil contamination from leaks of petroleum or other liquids, CCR-related soil or groundwater contamination, and the presence of asbestos, PCBs, lead, or other regulated materials
- ***For Drake, the target is a flat, grassy brownfield with no remaining above-ground structures and subterranean structures strategically and safely abandoned.***



Decommissioning Target, continued

Greenfield

- Indicates remediation of a site suitable for residential redevelopment, where the extent of environmental cleanup satisfies local requirements, but does not return a site to preconstruction conditions.



Decommissioning Future: Vision



Decommissioning Approach

Decommissioning Plan is the overall planning activity for the complete decommissioning of a plant or site.

Decommissioning Plan is broken into Subplans to manage scope:

- Decommissioning Safety
- Decommissioning Staffing & Resource
- Site Security
- Coal Pile Management
- Chemical Management
- Regulated Construction Materials (Includes asbestos and lead paint)
- Asset Use and Salvage
- Deconstruction
- Remediation and Site Restoration



Decommissioning Scope

Phase 1

- Majority of the site scope
- Units retired when GSU's unplugged
- Completed when Drake Plant physical deconstruction is finished

Phase 2

- Commences when TNGG units have all been relocated
- Completed after TNGG site has been deconstructed



Decommissioning Approach

Leverage the industry experience of consultant (Burns & McDonnell) to ensure we have appropriately planned and have a solid Statement of Work.

- Ensure we are judicious with need and level of engagement
- Greatest area of engagement will be:
 - Initial plan review
 - Support for Deconstruction contractor Statement of Work



Decommissioning Scope

Phase 1

- Development of Deconstruction Scope of Work (Burns & McDonnell)
- Salvage Value
- Move GSU's for TNGG: Unit is retired when GSU is disconnected
- Disconnect equipment / isolate services
 - Remove coal, oil, water, natural gas, hydrogen (no heat, temporary lighting)
- Commence abatement (asbestos, lead):
Select contractor
- Deconstruction
- Remediation

Other Activities

- Rail spur endpoint
- Easements
- Legal



Decommissioning Approach

Plant Staff

- Collect drawings (OEG)
- Disconnect all equipment
- Drain all systems
- Plant isolation at site boundary
- Remove / dispose oil, greases, solvents
- Drain water
- Remove / purge Hydrogen
- Relocate salvageable equipment (to Front Range, Nixon, Remotes)
- Contractor coordination, Point-of-Contact Support



Decommissioning Approach, continued

Decommissioning Budget Estimate:

- 9 Colorado coal plants (Burns & McDonnell study)
- 2017 Study Decommissioning US Power Plants
(<https://media.rff.org/documents/RFF20Rpt20Decommissioning20Power20Plants.pdf>)
- Coal residual and Lead / Asbestos are high uncertainty



Deconstruction Approach

Statement of Work

Developed by Burns & McDonnell
Sufficient detail to decom Drake & Birdsall
Structured sufficiently to be used for Nixon and Birdsall

Deconstruction Endpoint

Brownfield

Soil Remediation

TBD / Material Management Plan

Historical building designation

None

Buildings/structure demo

All aboveground structures
Future: TNGG relocated / deconstructed

Stacks

Muncher/nibbler or explosives

Basements

Filled with crushed concrete

Circ Water Lines

Filled with controllable density fill (CDF)

Deconstruction Approach

Shooting vs. Tripping

- The industry standard has been for years to piece the boiler to the ground.
Risk-men and equipment in the fall radius of the equipment
- The second phase was to trip the boiler.
Risk-Men an equipment outside of the fall radius, but still in close proximity of the fall
- The latest phase is to shoot the structure.
Risk-Men and equipment outside are outside of the radius of the fall. By far the safest approach when done using the best available engineering



Decommissioning asset use and salvage

Salvage Approach

- ESD, Utilities, Contractor

Departmental Assessment

- Warehouse parts review
- Key Systems / components: to other plants or salvage
- Air compressors: some to be reused
- Other equipment?

Utilities

- Other departments potential uses
- Office furniture
- IT (servers, equipment)

Contractor

- Include in bid. Deconstruction contractor manages salvage.



Quiz Answers:

How many coal plants were retired during the period of 2015-2020?	122
How many land-based LM2500's are installed in the US?	231
What aircraft is the LM2500 engine commonly found on?	DC10

Contact Info: Tom Cook, Colorado Springs Utilities, tcook@csu.org





Colorado Springs Utilities[®]

It's how we're all connected